




PIN OUT

IDC 10PIN FEMALE DB9PIN FEMALE

1	RED LINE	1
2		2
3		3
4		4
5		5
6		6
7		7
8		8
9		9

F2WDB-1009-F18C-LF
LEADFREE

RoHS Compliant

***CONSTRUCTION:

1.CABLE:

* UL2651 28AWG*10C PITCH=1.27mm GRAY JACKET.

***CONNECTORS:

2.IDC SOCKET:

* IDC 10PIN SOCKET WITH POLARIZED.
* PINS: PHOSPHOR BRONZE WITH GOLD PLATED.
* INSULATOR: BLACK THERMOPLASTIC UL 94V-0
RATED PITCH: 2.54mm.

3.DB9F:

* D-SUB 9PIN FEMALE PANEL SOLDER TYPE.
* PINS: BRASS WITH GOLD PLATED.
* INSULATOR: BLACK COLOR P.B.T UL 94V-0 RATED.
* SHELL: STEEL WITH NICKEL PLATED.
* SCREWLOCKS: 5.0*9.4mm, 4-40UNC 2PCS.

4.TEST:

* CT: 2 ohm IS: 5M ohm.

5.PACKING:

* PACK EACH CABLE IN A POLY BAG.

6.MATERIAL:

* MATERIAL WITH RoHS GRADE

MORETHANALL
CONNECTORS
ASSEMBLIES

PART NO. F2WDB-1009-F18C

DWG NO. F2WDB-1009-F18C

FILE NO.

UNIT / mm

SCALE 1:1

CHECKED BY CY

DRAWING BY

PROJECTION



TOLERANCES ARE

.X ± 0.2
.XX ±
.XXX ±
AWG

DESCRIPTION:

IDC SOCKET 10PIN FEMALE TO
PANEL DB9PIN FEMALE

AREA

REVISIONS

HK

DATE

煜倫股份有限公司

